



FITZPATRICK HEATING COOLING LLC

Henniker town hall
\$47,07545

Furnish and install (4) Mitsubishi ductless Heat pumps systems in your town hall

All Material must be paid before start of job. Labor will be paid when project is complete

This is a quote to install (9) evaporators, (4) Condensers

NH saves is offering rebates up \$250 per ton. 5 ton Max per home.

Quote is only good for one month with COVID-19. Material pricing is constantly changing.

It's a pleasure to work with you on this project, Please feel free to ask any questions.

%4 additional Charge if paid with Credit Card

Material cost is **\$36,875.45**

Thank you for this opportunity,
Connor Fitzpatrick
603 260 7519
25 Elm AVE Antrim NH 03440
Cfitzpatrick89@gmail.com

Henniker Town Hall

I will be install multiple units throughout the first floor of the building.

There will be a Cassette in the following areas,

Main Lobby 12,000BTU

End of lobby hall 12,000BTU

Clerks office 9,000BTU

Assessing Department 9,000BTU

Conference Room 12,000BTU

Select/ Plannging office 12,000BTU

There will be standard wall mounted units going in,

Finance 6,000BTU

Town Administrator Office 6,000BTU

Dinet 12,000BTU

We will be running these units off of 4 Condensers outside. There will be two on the south side of the build and two on the north side of the building. This is quoted to be installed during regular bussiness hours, there could be a seperate quote to have the work done during off hours. The unit going in the conference room and selectmanspace can hold off until after construction of wall inbetween the space is completed.

Fitzpatrick Heating and Cooling LLC will provide the electrician for the work.

Fitzpatrick Heating and Cooling LLC will start on project as soon material is available.

**PROPOSAL SHEET
TOWN OF HENNIKER, NEW HAMPSHIRE**

**Ductless Mini Split Heating and Cooling
Systems**

The undersigned hereby offers, in accordance with the terms, conditions and specifications the request, to furnish all labor and equipment as follows:

Quantity	Unit	Description of interior Wall Mounted Units	Delivered & Installed	Extended Price
5	EA	Mitsu - SLZ-KP12NA	9-16-22	\$4,615.87
1	EA	Mitsu - MSZ-GL12NA	9-16-22	\$744.68
2	EA	Mitsu - MSZ-GL06NA	9-16-22	\$1,142.65
1	EA	Mitsu - MLZ-KP12NA	9-16-22	\$1,037.61

*Quantity on Interior Wall Mounted Units Shall Equal 9

Quantity	Unit	Description	Delivered & Installed	Extended Price
2	EA	Exterior Unit(s) SIZE 20,000 BTU	9-16-22	\$4,158.98
1	EA	Exterior Unit(s) SIZE 24,000 BTU	9-16-22	\$2,857.48
1	EA	Exterior Unit(s) SIZE 30,000 BTU	9-16-22	\$3,213.60
		Exterior Unit(s) SIZE BTU		
		Exterior Unit(s) SIZE BTU		
LUMP SUM		Electrical, Wire, Conduit, Disconnect, Piping & Miscellaneous Materials	9-16-22	\$17,404.58
LUMP SUM		Training		
1	EA	5 Year Minimum Equipment Warranty	9-16-22	—
1	EA	1 Year Installation Warranty	9-16-22	—
Delivery & Installation Completion Date Expectation				

THE UNDERSIGNED ACKNOWLEDGES:

- A. That he/she is an authorized agent of the firm submitting this proposal.
- B. The firm submitting this proposal has never defaulted on any municipal or federal government contract.

Company: Fitzpatrick Heating Cooling LLC

Signed By: 

Printed or Typed Name: Connor Fitzpatrick

Address: 25 ELM Ave Antrim NH 03440

Phone: 603-260-7519

Email: CFitzpatrick89@gmail.com

Primary Contact Name: Connor Fitzpatrick

Primary Contact Phone:

Email:

Please Return this Form with Bid Proposal to:

Henniker Town Hall
18 Depot Hill Road
Henniker, NH 03242.