



1252 County Road, New London, NH 03257
603-526-4049 / 603-526-4205
hansenbridge@tds.net

BRIDGE REPAIR ESTIMATE

June 13, 2022

CLIENT:
Town Of Henniker
Attn: Leo Aucoin
603-428-7200
roadagent@henniker.org

RE: Bridge Repair, Patterson Hill Bridge

Payment: Prior written approval in the form of a change order will be required before any additional work can be executed. An additional work price outline and change order form is provided for your convenience upon request.

Payment Schedule : #1 \$67,300.00 deposit prior to construction.

Payment Schedule : #2 \$67,300.00 due upon completion.

Description: Remove the existing timber deck, brush curbs and replace in kind. Remove and replace existing damaged w beam on bridge. Install barrier membrane between layers of pavement.

REPAIR ITEMS

Table with 3 columns: Description, Estimated Qty, Unit. Rows include Pressure Treated Deck, Pressure Treated Brush Curbs, W Beam, Galvanized Hardware, Barrier Membrane, Existing Pavement Removal, Rust Treating Of Impacted Areas, and Containment Device.

TOTAL \$134,600.00

- Price is based on Hansen Bridge to provide job supervision.
Price includes MUTCD road closure & detour signage.
Price includes removal and disposal of the existing deck, curbs, and rail.

Acceptance of above contract by owner, Date Signature

Thank you,
Hansen Bridge LLC.
Michael Hansen, President