

**Wastewater Treatment Collection System Maintenance
Bid 2022**

The Town of Henniker is inviting bid pricing for the maintenance of the Town's collection system. The work is outlined in the scope of work 1 thru 7. The cost for cleaning and televising should be listed separate with a desired project completion date of no later than September 15th, 2022.

The proposal should include 2 operators per truck, screens to catch debris at the discharge side of manholes, traffic control w/sign package, traffic cones and all required safety measurers per State of New Hampshire guidelines. Responders will provide reports (1 hardcopy & 1 digital) of completed work including recommended repairs to sewer mains and manholes. The Town of Henniker Wastewater Superintendent will notify the State for work performed on State roads, supply water from inch and a half service at WWTP, Fire Dept. or pumped from river and a disposal site for debris and wastewater.

The Town of Henniker request that the work be performed by the successful bidders own personnel. Any subcontractors must be approved by the Wastewater Superintendent.

Bid price proposals must be on company letterhead clearly stating an outline of cost per line item. The bid price shall include all increases in labor, administration, and materials for the duration of the contract. No change order in contract price will be permitted.

All work to be done under the direction of the Wastewater Superintendent. The Town of Henniker reserves the right to modify or reduce the scope based on the needs of the Town. Additional work may be added at the Town's sole discretion.

All bids must be submitted in sealed envelopes, addressed to the Town of Henniker in care of Ms. Wendy Baker, Executive Secretary and plainly marked with the name of the bid and the time of the bid opening.

The Town of Henniker will accept proposals/bids at Town of Henniker, 18 Depot Hill Road, Henniker, NH 03242 until 2:00 pm on March 31, 2022 at which time they will be opened publicly and read aloud.

Prospective bidders will be evaluated on the following criteria:

1. Price;
2. Bidders ability to perform within the specified time limits;
3. Bidders experience and reputation, including past performance for the Town;
4. Quality of the materials and services specified in the bid;
5. Bidders ability to meet other terms and conditions, including insurance and bond requirements;
6. Bidders financial responsibility;
7. Bidders availability to provide future service, maintenance and support;
8. Nature and size of bidder, and
9. Any other factors that the Board of Selectmen determines are relevant and appropriate in connection with a given project or service.

The Town of Henniker reserves the right to reject any and all bids, re-bid, negotiate any contracts, to waive irregularities in the proposal, and to accept the proposal which, in the Town's sole discretion, best serves the interest of the Town, and waive any formalities in the bid process.

The contractor will be required to provide an insurance certificate confirming the following insurance coverage; workers compensation insurance as required by the State of NH; broad-form comprehensive general liability insurance in the amount no less than \$1,000,000 combined single limit per occurrence; and vehicle insurance to include bodily injury, property damage, uninsured motorist, and employer's non-ownership coverage in the amount no less than \$1,000,000 combined single limit per occurrence. Contractor may be required and shall be prepared to post a bond or letter of credit to cover 1.5X the bid price upon request of the Board of Selectmen.

The contractor must also agree in writing to indemnify the Town of Henniker from any and all liability, loss or damage, including but not limited to bodily injury, illness, death or property damage, which the Town becomes legally obligated to pay as a result of claims, demands, cost, or judgment against the Town arising out of the contractor's actions or omissions relating to this project.

Other questions regarding this request for bids may be directed to Wastewater Superintendent. Ken Levesque at (603)428-7215.

2022 SCOPE OF WORK

<u>LOCATION</u>	<u>PIPE SIZE</u>	<u>LENGTH</u>
1. Western Ave.	8"	2975'
2. Old Hillsboro Road	8"	503'
3. Liberty Hill Road	8"	807'
4. Western Ave.	8" & 10"	2218'
5. Fairview Ave.	8"	1774'
6. Juniper Ridge	8"	1971'
7. Hall Ave.	8"	<u>2515'</u>
	TOTAL	12,763'

THERE WILL BE NO DUMPING OF WATER BACK INTO THE SEWER MAIN.

VACCUM WILL BE USED THE ENTIRE TIME WHILE CLEANING.

ALL DEBRIS WILL BE DISPOSED OF AT THE WWTP.

SCOPE OF WORK DETAILS

1. Western Ave. (8")

<u>Manhole #'s</u>	<u>Distance</u>
24 - 41	88'
41 - 42	136'
42 - 44	295'
44 - 46	264'
46 - 47	289'
47 - 48	290'
48 - 50	286'
50 - 51	298'
51 - 52	313'
52 - 53	297'
53 - 54	290'
54 - 55	<u>129'</u>
TOTAL	2,975'

Traffic Control and Sign Package Required

2. Old Hillsboro Road (8")

<u>Manhole #'s</u>	<u>Distance</u>
55 - OHR1	172'
OHR1 - OHR2	127'
OHR2 - OHR3	<u>204'</u>
TOTAL	503'

Traffic Control and Sign Package Required

SCOPE OF WORK DETAILS

3. Liberty Hill Road (8")

<u>Manhole #'s</u>	<u>Distance</u>
47 - 111	296'
111 - 112	285'
112 - 113	<u>226'</u>
TOTAL	807'

Traffic Control and Sign Package Required

4. Western Ave. (10"&8")

<u>Manhole #'s</u>	<u>Distance</u>
16 - 17	10" 123'
17 - 18	208'
18 - 19	288'
19 - 20	214'
20 - 21	254'
21 - 22	90'
33 - 34	8" 100'
34 - 35	146'
35 - 36	98'
36 - 37	135'
37 - 38	295'
38 - 39	159'
39 - 40	<u>108'</u>
TOTAL	2,218'

Traffic Control and Sign Package Required

SCOPE OF WORK DETAILS

5. Fairview Ave. (8")

<u>Manhole #'s</u>	<u>Distance</u>
98 - 97	287'
97 - 96	38'
96 - 95	291'
95 - 94	115'
94 - 38	148'
85 - 99	66'
99 - 100	135'
100 - 101	204'
101 - 102	248'
102 - 103	<u>242'</u>
TOTAL	1,774'

Traffic Control and Sign Package Required

6. Juniper Ridge (8")

<u>Manhole #'s</u>	<u>Distance</u>
103 - 104	180'
104 - J1	128'
J1 - 105	89'
105 - 106	214'
106 - 107	186'
J1 - J2	358'
J2 - J3	273'
J3 - J4	182'
J4 - J5	<u>361'</u>
TOTAL	1,971'

Traffic Control and Sign Package Required

SCOPE OF WORK DETAILS

7
8. Hall Ave. (8")

<u>Manhole #'s</u>	<u>Distance</u>
18 - 83	301'
83 - 84	198'
84 - 85	276'
85 - 86	227'
86 - 87	134'
87 - 88	205'
88 - 89	245'
89 - 90	303'
90 - 91	289'
91 - 92	204'
92 - 93	<u>133'</u>
TOTAL	2,515'

Traffic Control and Sign Package Required