



**Town of Henniker  
Wastewater Treatment Collection System Maintenance  
Bid 2021**

The Town of Henniker is inviting bid pricing for the maintenance of the Town's collection system. The work is outlined in the scope of work 1 thru 11. The cost for cleaning and televising should be listed separate with a desired project completion date of no later than October 1<sup>st</sup>, 2021.

The proposal should include 2 operators per truck, screens to catch debris at the discharge side of manholes, traffic control w/sign package, traffic cones and all required safety measurers per State of New Hampshire guidelines. Responders will provide reports (1 hardcopy & 1 digital) of completed work including recommended repairs to sewer mains and manholes. The Town of Henniker Wastewater Superintendent will notify the State for work performed on State roads, supply water from inch and a half service at WWTP, Fire Dept. or pumped from river and a disposal site for debris and wastewater.

The Town of Henniker request that the work be performed by the successful bidders own personnel. Any subcontractors must be approved by the Wastewater Superintendent.

Bid price proposals must be on company letterhead clearly stating an outline of cost per line item. The bid price shall include all increases in labor, administration, and materials for the duration of the contract. No change order in contract price will be permitted.

All work to be done under the direction of the Wastewater Superintendent. The Town of Henniker reserves the right to modify or reduce the scope based on the needs of the Town. Additional work may be added at the Town's sole discretion.

All bids must be submitted in sealed envelopes, addressed to the Town of Henniker in care of Mr. Joseph R. Devine, Jr, Town Administrator and plainly marked with the name of the bid and the time of the bid opening.

**The Town of Henniker will accept proposals/bids at Town of Henniker, 18 Depot Hill Road, Henniker, NH 03242 until 2:00 pm on May 6, 2021 at which time they will be opened publicly and read aloud.**

Prospective bidders will be evaluated on the following criteria:

1. Price;
2. Bidders ability to perform within the specified time limits;
3. Bidders experience and reputation, including past performance for the Town;
4. Quality of the materials and services specified in the bid;
5. Bidders ability to meet other terms and conditions, including insurance and bond requirements;
6. Bidders financial responsibility;
7. Bidders availability to provide future service, maintenance and support;
8. Nature and size of bidder, and
9. Any other factors that the Board of Selectmen determines are relevant and appropriate in connection with a given project or service.

The Town of Henniker reserves the right to reject any and all bids, re-bid, negotiate any contracts, to waive irregularities in the proposal, and to accept the proposal which, in the Town's sole discretion, best serves the interest of the Town, and waive any formalities in the bid process.

The contractor will be required to provide an insurance certificate confirming the following insurance coverage; workers compensation insurance as required by the State of NH; broad-form comprehensive general liability insurance in the amount no less than \$1,000,000 combined single limit per occurrence; and vehicle insurance to include bodily injury, property damage, uninsured motorist, and employer's non-ownership coverage in the amount no less than \$1,000,000 combined single limit per occurrence. Contractor may be required and shall be prepared to post a bond or letter of credit to cover 1.5X the bid price upon request of the Board of Selectmen.

The contractor must also agree in writing to indemnify the Town of Henniker from any and all liability, loss or damage, including but not limited to bodily injury, illness, death or property damage, which the Town becomes legally obligated to pay as a result of claims, demands, cost, or judgment against the Town arising out of the contractor's actions or omissions relating to this project.

Other questions regarding this request for bids may be directed to Wastewater Superintendent, Ken Levesque at (603) 428-7215.

# 2021 SCOPE OF WORK

LOCATION	PIPE SIZE	LENGTH
1. Hillside Drive	8"	3139'
2. Rush Road	8"	1801'
3. Depot Hill Road	8"	1697'
4. Pike Street	8"	655'
5. Flanders Road (use to be Gulf Rd.)	8"	694'
6. Cressey Street	8"	619'
7. Weare Road (South Rte. 114)	8"	727'
8. Water Street (South)	10"	1049'
9. Pearl Street	8"	443'
10. Weare Road (North Rte. 114)	8"	815'
11. Water Street (North)	10"	<u>1508'</u>
	<b>TOTAL</b>	<b>13,147'</b>

**THERE WILL BE NO DUMPING OF WATER BACK INTO THE SEWER MAIN.**

**VACCUUM WILL BE USED THE ENTIRE TIME WHILE CLEANING.**

**ALL DEBRIS WILL BE DISPOSED OF AT THE WWTP.**

## SCOPE OF WORK DETAILS

### 1. Hillside Drive (8")

<u>Manhole #'s</u>	<u>Distance</u>
66 - H1	358'
H1 - H2	252'
H2 - H3	289'
H3 - H4	298'
H4 - H5	295'
H5 - H5A	175'
H1 - H6	215'
H6 - H7	246'
H7 - H8	173'
H8 - H9	26'
H9 - H10	172'
H10- H11	200'
H11- H12	244'
H12- H13	<u>196'</u>
<b>TOTAL</b>	<b>3,139'</b>

Traffic Control and Sign Package Required

### 2. Rush Road (8")

<u>Manhole #'s</u>	<u>Distance</u>
60A - 61	235'
61 - 62	171'
62 - 63	134'
63 - 64	215'
64 - 65	295'
65 - 66	286'
66 - 67	286'
67 - 68	<u>179'</u>
<b>TOTAL</b>	<b>1,801'</b>

Traffic Control and Sign Package Required  
Rush Road is a State Road

## SCOPE OF WORK DETAILS

### 3. Depot Hill Road (8")

<u>Manhole #'s</u>	<u>Distance</u>
144 - 148	30'
148 - 149	124'
149 - 150	265'
150 - 151	262'
151 - 152	216'
152 - 153	285'
144 - 145	46'
145 - 146	68'
146 - 147	201'
147 - 147A	<u>200'</u>
<b>TOTAL</b>	<b>1,697'</b>

Traffic Control and Sign Package Required

### 4. Pike Street (8")

<u>Manhole #'s</u>	<u>Distance</u>
141 - 142	110'
142 - 143	260'
143 - 144	<u>285'</u>
<b>TOTAL</b>	<b>655'</b>

Traffic Control and Sign Package Required

## SCOPE OF WORK DETAILS

### 5. Flanders Road (8")

<u>Manhole #'s</u>	<u>Distance</u>
141 - G1	298'
G1 - G2	271'
G2 - G3	<u>125'</u>
<b>TOTAL</b>	<b>694'</b>

Traffic Control and Sign Package Required

### 6. Cressey Street (8")

<u>Manhole #'s</u>	<u>Distance</u>
C1 - C2	250'
C2 - C3	155'
C3 - C4	180'
C1 - 164	<u>34'</u>
<b>TOTAL</b>	<b>619'</b>

Traffic Control and Sign Package Required

### 7. Weare Road (South, Rte. 114)(8")

<u>Manhole #'s</u>	<u>Distance</u>
139 - 162	76'
162 - 163	209'
163 - 164	252'
164 - 165	<u>190'</u>
<b>TOTAL</b>	<b>727'</b>

Traffic Control and Sign Package Required  
Weare Road is a State Road

## SCOPE OF WORK DETAILS

### 8. Water Street (South) (10")

<u>Manhole #'s</u>	<u>Distance</u>
Syphon Chamber - 135	136'
135 - 136	267'
136 - 138	270'
138 - 139	216'
139 - 141	<u>160'</u>
<b>TOTAL</b>	<b>1,049'</b>

Traffic Control and Sign Package Required

### 9. Pearl Street (8")

<u>Manhole #'s</u>	<u>Distance</u>
169 - 170	50'
170 - 171	192'
171 - 172	<u>201'</u>
<b>TOTAL</b>	<b>443'</b>

Traffic Control and Sign Package Required

### 10. Weare Road (North, Rte. 114) (8")

<u>Manhole #'s</u>	<u>Distance</u>
130 - 131	137'
131 - 132	57'
132 - 133	170'
133 - 134	130'
134 - 169	<u>321'</u>
<b>TOTAL</b>	<b>815'</b>

Traffic Control and Sign Package Required

Weare Road is a State Road

## SCOPE OF WORK DETAILS

### 11. Water Street (North)(10")

<u>Manhole #'s</u>	<u>Distance</u>
Syphon Chamber - 121	142'
121 - 122	295'
122 - 123	163'
123 - 124	179'
124 - 125	167'
125 - 126	113'
126 - 127	73'
127 - 128	223'
128 - 129	76'
129 - 130	<u>77'</u>
<b>TOTAL</b>	<b>1,508'</b>

Traffic Control and Sign Package Required